

Worldwide Pollution Control Association

**Dry Scrubbing
O&M Training**

**APC/PCUG Conference
July 12-16, 2009
The Woodlands, TX**



Visit our website at www.wpca.info

**W
P
C
A**



White Bluff Environmental Project

Entergy Arkansas

Presenter: Camille Carmena

White Bluff Plant

- Redfield, AR on Arkansas River about 25 miles south of Little Rock
- Unit 1: 880/815 MW
- Unit 2: 880/844 MW
- Commissioned in 1980 & 81
- CE drum-type units
- Dual furnaces, tangentially fired
- PRB fuel
- Stacked precipitators
- Hot side to cold side conversion shortly after initial operation of units



Project Goals

- Reduce both NO_x and SO₂ to 0.15 lb/mmbtu, calculated on a 30-day rolling average for PRB fuel.
- The level of emissions reduction has been mandated by the state of Arkansas to carry out its obligations under the Clean Air Visibility Rule.
- The regulation also stipulates that the controls must be operational no later than October 2013.

Project Overview

- **Entergy's only FGD project (Independence Plant is not affected)**
- **Sargent & Lundy – Owner's Engineer**
- **Conceptual design studies completed including:**
 - **Wet vs Dry Technology**
 - **Draft System**
 - **Material Handling**
 - **Byproduct Disposal**
- **PowerAdvocate – All specifications and bid information is available online and bid proposals are submitted via a confidential, web-based application.**

Wet vs Dry Study

- Based on S&L's study and cost assessment, a lime spray dryer with baghouse was chosen as the low cost technology.
- Desire to accommodate higher SO₂ levels on occasions when PRB coal supply is not adequate.

Unit 1 & 2 Design Basis

- **Gross Load: 880 MW_g**
- **Heat Input:**
8950 mmBtu/hr
- **MCR Flow Rate:**
3.7 mmACFM
@ 318 °F & 14.58 psia
- **Air heater outlet: ~300°F**
- **PM loading: 0.05 gr/acf**
- **Fuel**
 - PRB
 - 2.0 lb SO₂/mmBtu
- **Water**
 - Cooling tower
blowdown: 390 ppm
Cl

Draft System Study

- The decision was made to proceed with a dry FGD and fabric filter with existing ID fans and new booster fans.
- The design will include 2 x 50% axial-type booster fans downstream of the fabric filters.
- The existing ID fans will not be replaced or altered during FGD implementation.

Other project decisions...

- **Will reuse the existing concrete chimney which has dual carbon steel liners.**
 - **Top 50' of each liner is 316 stainless steel.**
 - **Will apply an acid-resistant coating to the top 100' of shell to prevent damage from tip downwash.**

Other project decisions...


- No new landfill. Byproduct will go in existing landfill.
- ESPs will remain in service to allow continuation of ash sales.
- Site visits included Louisa and Brayton Point.
- Based on byproduct analyses from those sites, we intend to blend:
 - 65% byproduct
 - 30% water
 - 5% fly ash

Contracts

- **Contracts:**
 - FGD Island – furnish and erect
 - BOP – furnish and erect
 - NOx Reduction – Low NOx burners & SOFA (separated overfire air)

Entergy White Bluff

Dry FGD Specified Scope



FGD Scope

- **The FGD EPC scope of work will include engineering, procurement and construction of:**
 - reagent preparation, recycle system, spray dryers, baghouse, booster fans,
- **DCS design and commissioning and startup.**


BOP Scope

- The BOP EPC contractor is expected to take responsibility for the overall project schedule.
- The BOP EPC scope of work will include engineering, procurement and construction of:
 - Reagent handling including rail spur, unloading, and storage
 - Byproduct handling including material handling systems, storage silos, discharge to trucks, and haul road
 - Process water retention pond
 - Chimney external coating
 - Auxiliary electrical system modifications and distribution systems
 - Electrical associated with the spray dryers, baghouse, booster fans
 - All foundations associated with both BOP and FGD Island contracts.
 - Supply, installation, and integration of controls for FGD Island and BOP processes
- Additionally, the BOP EPC scope will include overall project and site construction management and schedule coordination with the FGD supplier.

Schedule

- Anticipate receiving air permit by year end.
- FGD RFP was issued March 2009; bids received in June 2009. Plan to award later this year.
- Preparing BOP RFP for issuance soon. Plan to award early 2010.
- Unit 1 tie-in outage – Fall 2012
- Unit 2 tie-in outage – Spring 2013

Demolition - Relocation Plan




Barge Delivery Haul Road



Barge Delivery Access




Dry FGD General Arrangement





Pre-Scrubber View



Post Scrubber Rendition



Questions?